

AMENDMENT 0001 NOTES:

As stated in the SOW, the design shall not exceed the requirements for regional permit approval level (would not require an individual permit from the USACE), and will be kept above the Mean Low Water (MLW) mark to the greatest extent possible.

The Navy requests no communication with property owner take place until agreement is signed and after kick-off between Navy and the selected Cooperator has occurred.

The proposal tasks should reflect the tasks indicated in the SOW. Additional breakout of subtasks, if desired, is acceptable. Also, the Cooperator must demonstrate/acknowledge they understand that if a task is not successfully completed as determined by the Navy, the Navy, at its discretion may cancel any and all remaining tasks.

As indicated in the SOW, an archaeological site is present within the project area. The site is a shell midden visible on the shore – there has been a lot of tidal/wave action re-deposition of prehistoric, historic and modern shell and midden materials in the spit area in which the project area is located and it is unclear how intact this portion of the archaeological site is but for the purposes of this project it will be treated as eligible for the National Register of Historic Places.

Protective measures to avoid an adverse effect on the archeological site will be negotiated between the Navy and the Virginia State Historic Preservation Officer. Cooperator will be responsible for ensuring measures are implemented. Measures are likely to include - no grading or ground cutting of the archaeological site (including grading/cutting of the existing banks such as to achieve a specific slope for the extent of the site along the shoreline); construction equipment storage and staging areas to avoid the archaeological site unless there are no other reasonable options; where temporary construction activities/access cannot avoid the site, a protective system would be employed during construction, covering the site area with geotextile fabric, protective clean fill and, if necessary, wooden mats. These measures will be removed by the Cooperator at the conclusion of construction with the possible exception of any protective measures placed over the archaeology site and incorporated as part of the designed solution.